
## Feedall automation



FEED FROM A RANDOM LOADED FLOOR MOUNTED HOPPER SHEARED STEEL BILLETS, 1.937 TO 2.625" DIA. X 2.00 TO 3.25" LG. THE BILLETS WILL BE ORIENTED IN TO A SINGLE END TO END STREAM, THEN TRANSFERRED ONE AT A TIME ROLLING IN TO A PUSHER DEVICE, WHICH WILL ADVANCE EACH BILLET TO AN INDUCTION COIL AT 60" ABOVE THE FLOOR AT A RATE OF 350 TO 450 PER. HOUR FOR FORGING. 12" WIDE ELEVATOR BELT, 30 CU. FT. HOPPER. DWG PD 7152